

DRILLING DEPTH RATING:

Drilling 20,000' w/5" drill pipe

LIGHTSHIP:

(Towing Draft) 6'6"

(Towing Height) 62'

BARGE DIMENSIONS, SPECIFICATIONS:

Length	205'
Beam	50'
Hull Depth	14'
Key Slot	57' x 10'
Main Deck to Rotary Pan	24'2"
Accommodations	38 bunks
Helipad	68' x 47'

CAPACITIES:

Potable water	40,000 gallons
Drill water	5,000 barrels
Mud tank capacity	1,435 barrels
Fuel	40,000 gallons
Bulk Barite	3,000 sacks



Equipped for full zero discharge operations for work within environmentally sensitive areas.

DRAWWORKS:

- Skytop Brewster NE-12 (2000 HP) w/7838 Elmago electric brake, driven by (2) GE 752 electric motors (2000 input HP)

MUD PUMPS:

- (2) C. E. FB-1600 (1600 HP) triplex pumps driven by (2) GE 752 (2000 HP) electric motors.

MAST AND TRAVELING EQUIPMENT:

- 142' Skytop Brewster cantilever mast with a static hook load of 1,000,000 lbs
- 500T Skytop Brewster 7 sheave crown
- 500T traveling block
- 500T CanRig top drive
- 27½" rotary table

WELL CONTROL EQUIPMENT:

- (1) ea. 13 5/8" 5,000 lb psi annular BOP
- (1) ea. 13 5/8" 10,000 lb. Double Ram BOP w/ blind shear
- (1) ea. 13 5/8" 10,000 lb. Single Ram BOP
- (1) ea. 10,000 lb. Choke Manifold
- 7 Station / 200 gal. closing unit
- Pneumatic BOP hoist

Note: Other BOP equipment available from stock



Note: equipment subject to client-specific requirements

Energy. Well engineered.

Find out more at parkerwellbore.com

©2021 Parker Wellbore. All Rights Reserved.

1110 Unifab Road
New Iberia, Louisiana 70560
Tel: 337.364.3122 Fax: 337.364-3292
Uncontrolled if printed • Date of issue 10/28/08

MUD HANDLING/SOLIDS CONTROL:

- (2) Shale shakers
- Desander
- Desilter
- Degasser
- Mud Agitators
- Mud mixing pumps
- (2) Derrick Flowlin Cleaner + (1) Derrick FLC513 Flowline Cleaner
- Derrick 3/10
- Derrick 4/20
- Brandt DG10
- (4) Brand MA-10
- (2) Bran MA-5
- (3) x 8 centrifugal pumps

POWER & ELECTRICAL SYSTEM:

- (3) 3512 Caterpillar (1500 HP) engines
- (3) KATO 1365 KW generator sets
- IPS Three Bridge SCR system

TUBULARS:

- 5" drill pipe, S-135 w/4 1/2" IF connections, w/handling tools
- 15 joints of 5" heviwate drill pipe, w/4 1/2" IF connections
- 15 total drill collars (8" w/ 6 5/8" REG conn., 7 1/4" w/5 1/2" REG conn., 6 1/2" w/4 1/2" XH conn.)
- (1) pipe barge for Contractor's tubulars

MISCELLANEOUS EQUIPMENT:

- (1) 20 Ton hydraulic crane
- (1) 10 Ton hydraulic crane
- (2) 50 bbl. trip tanks
- (1) 300 amp welding machine
- (1) Quincy Bulk air compressor
- (1) Quincy Model 5120 cold start air compressor
- (2) Quincy Model 245 air compressors
- (1) 10 X 30 Cantilever Deck - Shakers
- (1) 12 X 30 Cantilever Deck - Pipe Rack
- (1) .092 Wireline unit

