

DRILLING DEPTH RATING:

Drilling 25,000' w/5" drill pipe

LIGHTSHIP:

(Towing Draft) 7'

(Towing Height) 70.7'

BARGE DIMENSIONS, SPECIFICATIONS:

Length	224'
Beam	54'
Hull Depth	14'
Posted Deck Height	14'
Key Slot	55' x 10'
Main Deck to Rotary Pan	28.4'
Accommodations	59 bunks
Helipad	48' x 50'

CAPACITIES:

Potable water	59,633 gallons
Drill water	6,348 barrels
Mud tank capacity	1,414 barrels
Fuel	52,786 gallons
Bulk Barite	4,000 Sacks
Tear Drop Bulk Barite	75 Sacks



Equipped for full zero discharge operations for work within environmentally sensitive areas.

DRAWWORKS:

- Oilwell E-2000 (2000 HP) with 7838 Elmago electric brake, driven by (2) GE 752 electric motors (2000 HP)

MUD PUMPS:

- (2) Lewco 2215 (2200 HP) triplex pumps driven by (2) GE 752 High Torque motors (2200 input horsepower)
 - 7500 psi Working Pressure Mud System

MAST AND TRAVELING EQUIPMENT:

- 148' Pyramid cantilever mast with static hookload of 1,330,000#
- 750T Pyramid 7 sheave crown
- 750T block
- 650T CanRig Top Drive
- 37½" rotary table driven by (1) GE 752 electric motor
- (1) 7500 psi wp Rotary Hose

WELL CONTROL EQUIPMENT:

- (1) 13 5/8" 5,000 lb w.p. Annular BOP
- (1) 13 5/8" 10,000 lb. Double Ram BOP w/LBSBTB blind shear rams
- (1) 13 5/8" 10,000 lb. Single Ram BOP
- (1) 13 5/8" 10,000 lb. Drilling Spool
- 240 gal CAD Accumulator Unit
- 10,000 psi Choke Manifold

Note: Other BOP equipment available from stock

Note: equipment subject to client-specific requirements



Energy. Well engineered.

Find out more at parkerwellbore.com

©2021 Parker Wellbore. All Rights Reserved.



1005 RPC Energy Dr. Broussard, LA 70518
 Tel: 337.364.3122 Fax: 337.364-3292
 Uncontrolled if printed • Date of issue 1/25/08

MUD HANDLING/SOLIDS CONTROL:

- Shale shaker (4) Derrick Hyperpool
- Desander (3) Derrick 10" Hydrocyclone
- Desilter (20) Derrick 4" Hydrocyclone
- Degasser Vack 1200
- Mud Agitators (1) Brandt MA-25
- (3) Brandt MA-15
- (2) Brandt MA-5
- Mud mixing pumps (3) 6x8 centrifugal pump
- (2) Vortex shear hoppers

POWER & ELECTRICAL SYSTEM:

- (4) 3512 Caterpillar (1500 HP) engines
- (4) KATO 1365 kw generator sets
- (5) Bay SIEMENS Digital SCR System

MISCELLANEOUS EQUIPMENT:

- (1) 15 Ton Sea King cranes
- (1) 35 Ton Hydraulic crane
- (1) 100 bbl. trip tank w/2 4X3 pumps
- (2) 400 amp welding machines
- (1) Quincy Model QSI 60LP bulk air compressor
- (2) Quincy Model 245-A electric air compressors
- (1) Quincy Model cold start air compressor
- (1) 10' X 30' cantilever- Shakers
- (1) 12' X 30' cantilever - Pipe Rack

TUBULARS:

- 5" drill pipe w/handling tools
- 15 joints of heviwate
- 15 drill collars (8", 7 1/4", or 6 1/2")

